



US CMS TriDAS

US CMS Meeting

Wesley H. Smith, *U. Wisconsin*

CMS Trigger Project Manager

May 10, 2002

Outline:

Calorimeter Trigger Status & Plans


Muon Trigger Status & Plans

DAQ Status & Plans (from Vivian O'Dell)


This talk is available on:

http://hep.wisc.edu/wsmith/cms/TriDAS_USCMS_0502.pdf

L1 Trigger Hardware Overview




US CMS
Trigger
(this talk)





Calorimeter Trig.Overview





Cal. Trig 2nd Gen. Prototypes (U. Wisconsin)

New High-Speed Backplane

• 160 MHz with 0.4 Tbit/sec dataflow

- Designed to incorporate algorithm changes

- New Non-Isolated Electron, Tau & Jet Triggers

DC-DC converters

New Clock & Control Card


- Fans out 160 MHz clock & adjusts phases for all boards

- 50% tested successfully





New Cal. Trig. 4 Gbaud Copper Link Cards & Tester (U. Wisconsin)



8 Compact Mezzanine Cards for each

Card accept

4 x 20 m 1.2-Gbaud copper pairs transmitting 2 cal. tower energies every 25 ns with low cost & power.

Uses new Vitesse Link Chips (7216-01).


New Serial Link Test Card

Status: under test




New Calorimeter Trigger Receiver Card (U. Wisconsin)

Full featured final prototype board is in test - initial results are good.
Continue to test on-board ASICs & copper link mezzanine cards





*Top side with 1 of 8 mezzanine cards
& 2 of 3 Adder ASICs*

*Bottom side with all Phase
& Boundary Scan ASICs*



Cal. Trig. New Electron Isolation & Jet/Summary Cards (Wisconsin)






Cal Trigger Status/Plans

Preparing second generation prototype tests


- Crate, Backplane, Clock & Control, ASICs done
- Receiver Card & Electron Isolation Card ready.
- Serial Link Mezzanine Card Receiver done,
Tester Card at vendor, Transmitter Tester in design


Goals for 2002

- Complete of prototype tests, validate ASICs
- Integrate Serial Links w/ECAL,HCAL front-ends
- Prototype Jet/Summary card manufacture
 - Ready for manufacture -- waiting for other board tests
- Finalize Jet Cluster crate design



CSC Muon Trigger Scheme






1st Muon Trigger Prototypes (Florida, Rice, UCLA)


Successful CSC Trigger Integration test

- Prototype Muon Port Card, Sector Receiver, Sector Processor, Clock Board, Backplane work & communicate -- Result in 2000


ORCA full simulation working

- Agreement/use with hardware test






1st Track-Finder Crate Tests



*Custom
Backplane
(Florida)*


*Prototype
crate for
original six
crate design*

*Very
successful
but latency
too high --
New
design in
2001
100m optical
fibers*




Single Track-Finder Crate Design with 1.6 Gbit/s optical links

New EMU Trigger Design: U. Florida Track-Finder





- Reduces processing time from 525 ns (old design) to 175 ns
 - Total Latency ~ 20 BX (from input of SR/SP card to output of MS card)
- Crate Power Consumption ~ 500 W • 15 Optical connections per SR/SP card
- Custom Backplane for SR/SP ⇔ CCB and MS connection



New Muon Port Card Design & Optical Link Tests (Rice)

New MPC Design uses new high speed links (TLK2501) to send one muon per optical fiber (needed for new compact track-finder design)



Optical Link Radiation Tests:

Three serializers: up to 270 kRad TID.
No permanent damage or SEU

Two Finisar optical modules: No errors up to 70 kRad. Failed at 70kRad (well above ~10 kRad TID inner CSC dose for 10 years)



CSC Trigger Status/Plans

Prototype 1 tests now complete


Prototype 2 and production follow EMU components to optimize technology

MPC, SP, CCC modules, backplane* milestones:

- Apr-02 Prototype 2 designs done
 - Freeze CSC-DT interface
 - Determine DDU compatibility with OSU module for EMU
- Nov-02 Prototype 2 construction done
- Apr-03 Prototype 2 testing done
- Sep-03 Final designs done
- Oct-04 Production done
- Apr-05 Installation done

(*backplane schedule ~3 months ahead of above dates to provide platform for testing and integration)


Muon Sorter module: only 1, design by Jan-04



Schedule: Trigger Project Completion

Installation in Underground Counting Room

- Expect access by March '05
- Sufficient time for installation and some testing but not for completing commissioning with detectors



Slice Test (on surface)


With both HCAL and EMU

Verify trigger functions and interfaces by testing with detectors on surface at CERN.

Suggest as substitute for commissioning completion step.

Will check as much on surface before gaining access to underground facilities.

Planned for October '04 - March '05



Original Trigger L2 Task Schedule & Updates


Tasks

	original start	finish	new
• Produce TDR	8/00	12/00	✓
• Design Final Prototypes	11/00	12/01	✓
• Construct Final Prototypes	6/01	6/02	⇒ 11/02
• Test/Integrate Final Prototypes	12/01	12/02	⇒ 4/03
• Pre-Production Design & Test	6/02	6/03	⇒ 11/03
• Production	12/02	6/04	
• Production Test	6/03	11/04	
• Trigger System Tests	5/04	5/05	
• "Slice Test" NEW	10/04	3/05	
• Trigger Installation	3/05	9/05	
• Integration & Test w/DAQ & FE	6/05	12/05	
• Maintenance & Operations	10/04	↑

6 months civil engineering delay of installation date



DAQ System Overview






New DAQ design: principle

Basic principle:


- Break DAQ into a number of functionally identical, parallel, smaller DAQ systems

- A 64x64 system is feasible today







Detector readout to surface





D2S + RB + EF breakdown









DAQ: US contribution (old)

US: Event Manager + Builder Units

CERN:
Inputs(500)
+ Switch

US:
Outputs
+ EVM

US



Filter Units not included in
“outputs”

Other responsibilities:
Detector Front-Ends:
detector groups
Computing Services:
infrastructure



US contribution: new


Cover one segment (1/8) of the CMS DAQ plus of the Data-to-Surface system (plus the associated prototypes – “preseries”)

- Segment: 1 Readout Builder + 1 Event Filter
- US_CMS detector electronics is ~1/4 of the total
- Delivery of the system can be accomplished by the end of the **US_CMS project (FY05)**
- **Aids the experiment most in the current phase where cash flow is very tight**

- US R&D program can remain ~ unchanged (to the extent that the basic modules are the same)

Roughly speaking, the US

- (a) works on/delivers prototype system (to 2004)**
- (b) delivers the “startup DAQ” for CMS (2005)**



Milestones*

Prototype DAQ (US Contribution)

D2S Prototype

“Slice Test”

Readout Builder Prototype

July, 2004

November, 2004 (*)

April, 2005

Startup DAQ (US Contribution)

Filter Farm Ready

Readout Builder Ready

May, 2006

August, 2006

Declaration of Completion (US Contribution)

Startup DAQ ready for beam


September, 2006

(*) “Slice” Test for US-CMS detectors – DAQ will have full D2S proto + a few RB elements

*(Version 33)



Slice Test DAQ (10-100 Hz)



- Trigger system
 - Detector readout
 - Readout Units
 - Data to Surface
 - RCN, BCN, BDN networks
 - Event manager
 - Builder/Filter Units
 - Performances
- GTP, TTC and sTTs**
Complete **FED** crate systems (FED-TTC-TTS, Controller CPU+DSN)
XDAQ **RU-VME-tasks** running in all the **FED controllers**
None just the **FED-VME bus** of FED crates
DAQ Service Network (**DSN** e.g. GEthernet)
XDAQ **EVM-task** running in the **GTP controller**
XDAQ BU-task running in **any DSN(WAN) CPU**
Few 10 Hz (up to 100s when using GE switches in DSN as EVB)